

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: T.T. Production, Inc.
Address: R.R. #1 Box 91, Haviland, Ks. 67059
Phone: (620) 723-2944 Operator License #: 31929
Type of Well: Gas Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Eric McClernan (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15-097-20272-00-00
Lease Name: Stewart
Well Number: 1
Spot Location (QQQQ): C - SW - SE - SE
330 Feet from North / South Section Line
990 Feet from East / West Section Line
Sec. 26 Twp. 27 S. R. 18 East West
County: Kiowa
Date Well Completed: _____
Plugging Commenced: 12-19-05
Plugging Completed: 12-20-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	316	none
				4-1/2"	4784	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 4080', dumped 4 sacks of cement with bailer, cut casing at 2000'. Pulled 4-1/2" casing up to 1170', mixed 10 sacks of gel, 50 sacks of cement, 60/40 pos, 6% gel at 1170', pulled up to 330' and mixed 50 sacks of cement, pulled up to 40' and circulated 20 sacks of cement. Plugging Complete.

Name of Plugging Contractor: Mike's Testing & Salvage, Inc. License #: 31529
Address: P.O. Box 467 Chase, Kansas 67524
Name of Party Responsible for Plugging Fees: T.J. Production, Inc
State of Kansas County, Rice, ss.

RECEIVED
JAN 03 2006
KCC WICHITA

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 30th day of December, 20 05

[Signature]
Notary Public

My Commission Expires: _____

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 5-24-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Bm