

Conservation Division - Plugging Section
130 S. Market, Room #2078
Wichita, KS 67202
State Corporation Commission

RECEIVED
DEC 19 2005
KCC WICHITA

API Number: 15-095-05012-00-00 ⁰¹⁵⁰⁸⁻⁰⁰⁻⁰¹

SENWSE / Section: 27 Township: 29 Range: 7 WEST
1748 Feet from SOUTH section line
1746 Feet from EAST section line

Lease Name: VORAN C-3
County: KINGMAN

License #: 32215
Operator: RAKESTRAW BROS.
Address: 4556 N E PARALLEL RD
ELDORADO KS 67042

Well Total Depth: 5004'
Production Pipe: 5 1/2 4646'
Surface Casing: 8 5/8 @ 403'

Oil: Gas: EOR: SWD: DH: Other: _____

Plugging Contractor: ACID SERVICES License: 32453
Address: PRATT KS.
Plugging proposal received FROM: CURT RAKESTRAW Phone: 316-644-2713
Company Name: RAKESTRAW BROS. LLC.

Plugging Began: Hour: 0830 AM Month: 11 Day: 30 Year: 2005

Plugging instructions:

2 3/8 LINED TUBING CEMENTED IN HOLE. OH COMPLETED 4646'-5004'. TUBING SET AT 4606', CEMENTED TO SURFACE WITH 500 SKS OF HOWCO-LITE. PLUG ORDERS ARE, PUMP 30SKS OF CEMENT INTO O H LEAVE 50'-100' OF CEMENT IN PIPE. PERF AT AND SQUEEZE SKS OF CEMENT INTO PERFS. PERF AT AND SQUEEZE CMT INTO PERFS. PERF T 410' AND CIRC. CMT TO SURFACE.

Plugging proposal received BY: Steve Van Gieson

Plugging operations attended by agent? All: Partial: None:

Plugging Completed: Hour: 1545 AM Month: 11 Day: 30 Year: 2005

Actual plugging report:

DUG OUT WELLHEAD, FOUND CEMENT IN BRADEN HEAD, WILL NOT BE ABLE TO CIRC. TOP PLUG. PUMPED 30 SK PLUG DOWN TUBING TO PLUG O H. DISP. TO WITHIN 100' OF BOTTOM OF CASING. S.I. WAITING ON CEMENT TO SET. SHOT PERF HOLES AT 1250'. TIED ONTO TUBING AND PRESSURED UP TO 400#. WENT BACK IN WITH PERF GUN TO 750' HOLES. TIED ON PUMP TRUCK, GOT INJ. RATE AT 1.5 BBL/MIN. AT 0 PRESSURE. BEGAN PUMPING CEMENT AND GOT CIRCULATION TO SURFACE. PUMPED CEMENT UNTIL IT RETURNED TO SURFACE.

Remarks: ACID SERVICES COMMON 3% CACL

Well plugged through: Casing: Drill Pipe: Tubing: Other: _____

I DID observe this plugging

[Signature]
P.I.R.T.'s Name

INVOICED

DATE 12-21-05

TV. NO. 2006060893