

3 022716

15-207-19509-00-01

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20040041

NW SW,SW 1/4 Sec/Twp/Rge S.34-T.26S.-R.16E.

875 feet from south section line

4683 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well# APT NO. 10-I

Operator License # 101

County WOODSON

Operator: STATE OF KANSAS FeeFund

Well Total Depth 1000' feet

Name &amp; FEE FUND PLUGGING

Production Pipe: 2" Size Feet 1000'

Address

Surface Casing: 6" Size Feet 20'

AB oil well X Gas Well SWD Well/ Input Well

D &amp; A

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE

Lic. # 6372

Address: BOX 386, RR4, CHANUTE, KANSAS 66720

Company to plug at: Hour: 9:30A.M. Day: 13 Month: 4 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 1000' THAT HAD

BEEN CEMENTED IN AT T.D. ONLY. 1" PIPE HAD BEEN "LEFT HANDED" FROM THE WELL

TO 525'. PROBABLY 1" PIPE REMAINS IN THE WELL FROM 525' TO NEAR T.D.. THE PLUGGING

PROPOSAL IS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part

TECHNICIAN  
None X

Operations Completed: Hour: 12:30P.M. Day: 13 Month: 4 2005

Actual Plugging Report: 3/4" PIPE WAS RAN INTO THE 2" CASING TO 525'. CEMENT

WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT

SURFACE. THE 3/4" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2"&amp; 6" ANNULUS

TO 300'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM

THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS

FILLED FROM SURFACE. 69 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED

APR 28 2005

KCC WICHITA

Remarks: (GPS SESSION PT. NO. 73 ) ( THIS WELL WAS NO.10-I ON THE LEASE MAP. )

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

  
TECHNICIAN