

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-22034-00-00<sup>01</sup>  
Spot: NWNESE Sec/Twnshp/Rge: 10-16S-25W  
2310 feet from S Section Line, 990 feet from E Section Line  
Lease Name: GIESS D O W W O Well #: 2  
County: NESS Total Vertical Depth: 4552 feet

Operator License No.: 30742  
Op Name: PALOMINO PETROLEUM, INC.  
Address: 4924 SE 84TH STREET  
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4520	0	WITH 350 SX CMT
SURF	8.625	292		WITH 190 SX CMT #147 <sup>94</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/14/2005 1:00 PM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: ROGER LEGLEITER Company: SWIFT SERVICES Phone: \_\_\_\_\_

Proposed Plugging Method: SAND BACK TO 4415' & 5 SX CMT. PLUG AT 2070' WITH 50 SX CMT. PLUG AT 1500' WITH 115 SX CMT. PLUG AT 60' WITH 20 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/14/2005 4:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SANDED BACK TO 4415' & 5 SX CMT WITH DUMP BAILER. 1ST PLUG PUMP 50 SX COMMON CMT WITH 3% CC & HULLS AT 2070' THROUGH TUBING. LET SET 1 HOUR. CIRCULATE TO SURFACE. 2ND PLUG RUN TUBING BACK TO 1500' & PUMP 115 SX CMT WITH 400# HULLS TO SURFACE. GOOD CIRCULATION. 3RD PLUG TOP OFF 5 1/2" CASING WITH 20 SX CMT TO SURFACE. PUMP 20 SX CMT DOWN ANNULUS. PRESSURE TO 300# & HELD.

Perfs:


Top	Bot	Thru	Comments
4520	4540		

Remarks: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES.

Plugged through: TBG

**INVOICED**  
DATE 10-20-05  
INV. NO. 2006060651

District: 01



Signed Jerry W. Stapleton PIRT II  
(TECHNICIAN)

RECEIVED  
OCT 20 2005  
KCC WICHITA

Form SP 231