

3 022960

15-001-28217-00-01

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078  
Wichita, Kansas 67202

KCC  
BEM  
12-13-05  
RSDMS  
GPS Location

API NUMBER  
SESENE  
NE,NE,SE-1/4

CONTROL NO. 20060001-032

Sec/Twp/Rge S.24-T.26S.-R.17E.

2815 feet from south section line

550 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101 400

Operator: STATE OF KANSAS Fee Fund

Name & \_\_\_\_\_

Address \_\_\_\_\_

AB oil well \_\_\_\_\_ Gas Well \_\_\_\_\_ SWD Well/ Input Well E-25,284 D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: KEPLEY WELL SERVICE Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: \_\_\_\_\_ Day: 11 Month: 11 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO 820' THAT HAD BEEN  
CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO  
SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ TECHNICIAN  
None X

Operations Completed: Hour: \_\_\_\_\_ Day: 11 Month: 11 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO

THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE

CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL

THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 830PSI.

29 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED

DEC 09 2005

KCC WICHITA

Remarks: ( GPS SESSION PT. NO.38. ) (API NO. 15-001-28,217-00-01)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel  
TECHNICIAN

Bun