

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-20191-00-00
Spot: SWNW Sec/Twnshp/Rge: 20-5S-14E
2130 feet from N Section Line, 630 feet from W Section Line
Lease Name: BOHANNON Well #: 5-20
County: NEMAHA Total Vertical Depth: 2710 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2686		170 SX CMT
SURF	8.625	281		145 SX CMT # 88 ⁰⁸

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/21/2005 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2639' TO 2480', CMT FROM 2480' TO 2245', GEL FROM 2245' TO 300', CMT 300' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE
Date/Time Plugging Completed: 11/21/2005 12:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Pumped 30 sacks of cement and 1 sack of cottonseed hulls from 2492' to 2230'. Circulated 45 sacks of cement from 332' to surface. 75 sacks of cement total.

Perfs:

Top	Bot	Thru	Comments
2428	2430		
2399	2401		
2377	2379		
2362	2364		
2346	2348		
2311	2313		
2302	2304		
2295	2296		

RECEIVED
KCC DISTRICT #3

DEC 21 2005 ^{TC}

CHANUTE, KS

RECEIVED

JAN 03 2006

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)

INVOICED

DATE

1-3-06

INV. NO.

2006060932