

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API Well Number: 15-131-20177-00-00
 Spot: NESE Sec/Twnshp/Rge: 18-5S-14E
2030 feet from S Section Line, 660 feet from E Section Line
 Lease Name: ENGELKE Well #: 9-18
 County: NEMAHA Total Vertical Depth: 2692 feet

Operator License No.: 33233
 Op Name: HEARTLAND OIL & GAS, INC.
 Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2280		
PROD	5.5	2672		188 SX CMT
SURF	8.625	264		255 SX CMT

87⁴⁹

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/23/2005 8:30 AM
 Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
 Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed Plugging Method: GEL FROM 2629' TO 2474', CMT FROM 2474' TO 2245', GEL FROM 2242' TO 300', CMT 300' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE
 Date/Time Plugging Completed: 11/23/2005 12:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

After plugging application had been filed, a cast iron bridge plug was located at 2280'. Perfs were also found at 1773'-1877'. Pumped 25 sacks of cement and 1 sack of cottonseed hulls from 1924'-1707'. Circulated 40 sacks of cement from 312' to surface. 65 sacks of cement total.

Perfs:

Top	Bot	Thru	Comments
2422	2424		
2392	2394		
2366	2368		
2353	2355		
2336	2338		
2305	2307		
2301	2303		
2292	2294		
1773	1877		

RECEIVED
 KCC DISTRICT #3

DEC 21 2005 TCH

CHANUTE, KS

RECEIVED

JAN 03 2006

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Taylor C. Herman

(TECHNICIAN)

INVOICED

DATE 1-3-06
 INV. NO. 2006060932