

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-21039-00-00
Spot: N2NE Sec/Twnshp/Rge: 9-28S-40W
660 feet from N Section Line, 1250 feet from E Section Line
Lease Name: FLOYD Well #: 2-9R
County: STANTON Total Vertical Depth: 3148 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA.
Address: 5205 N. O'CONNOR BLVD.
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2350		31
CIBP		2435		#102
CIBP		2680		
CIBP		2700		
PROD	5.5	3147	0	WITH 540 SX CMT
SURF	8.625	669		WITH 375 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/01/2005 2:30 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS IN MUD THEN 60 SX CMT. PUMP MUD SPACER THEN 80 SX CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/01/2005 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 300# HULLS IN MUD FOLLOWED BY 60 SX CMT. PUMP MUD SPACER TO 700' FOLLOW WITH 95 SX CMT INSIDE 5 1/2" FROM 700' TO SURFACE. HOOK ONTO BACKSIDE & PUMP 3 SX CMT, FULL.

Perfs:

Top	Bot	Thru	Comments
2709	2796		
2516	2616		
2405	2422		
2208	2266		

RECEIVED
JAN 03 2006
KCC WICHITA


INVOICED

Remarks: USED COMMON CEMENT BY SARGENTS.

DATE 1-4-06
INV. NO 2006060947

Plugged through: CSG

District: 01



Signed

Jim Holland (TECHNICIAN)