

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20146-00-01
Spot: NENESENE Sec/Twnshp/Rge: 15-33S-42W
3880 feet from S Section Line, 132 feet from E Section Line
Lease Name: BOEHM Well #: 17
County: MORTON Total Vertical Depth: 5005 feet

Operator License No.: 7117
Op Name: COLORADO INTERSTATE GAS COMPA
Address: PO BOX 1087
COLORADO SPRINGS, CO 80944

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4700		WITH 25 SX CMT
CIBP		4805		WITH 2 SX CMT
COND	13.38	137		
PROD	5.5	4998	0	WITH 1025 SX CMT
SURF	9.625	81		
SURF	8.625	1378		WITH 750 SX CMT

Well Type: GSFCW UIC Docket No: S017.15 Date/Time to Plug: 12/20/2005 9:30 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: CHRIS Company: EAGLE WELL SERVICE Phone: (620) 624-1904

Proposed Plugging Method: SET CIBP @ 4700' WITH TBG, SPOT 20 SX CMT. TAG W/TBG. PULL UP 200', LOAD HOLE WITH MUD. PULL TO 1400', PUMP 40 SX CMT. PULL TO 690', PUMP 100 SX CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/22/2005 5:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

SET CIBP @ 4700' WITH 25 SX CMT ON TOP. 1ST PLUG AT 1400' WITH 30 SX CMT. 2ND PLUG AT 700' WITH 90 SX CMT TO SURFACE ALL INSIDE 5 1/2" CASING. PUMP 10 SX CMT DOWN BACKSIDE. PRESSURED TO 500# & SHUT IN.

Perfs:

Top	Bot	Thru	Comments
4828	4860		
4740	4762		

RECEIVED
JAN 04 2005
KCC WICHITA

RECEIVED
DEC 30 2005
KCC Dodge City

Remarks: USED COMMON CEMENT BY EAGLE WELL SERVICE.

Plugged through: TBG

District: 01

INVOICED

DATE 1-4-06
INV. NO. 2006060944

Signed

Jim Holland
(TECHNICIAN)