

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20124-00-00
Spot: SENENESE Sec/Twnshp/Rge: 15-33S-42W
2200 feet from S Section Line, 100 feet from E Section Line
Lease Name: BOEHM Well #: 11
County: MORTON Total Vertical Depth: 4825 feet

Operator License No.: 7117
Op Name: COLORADO INTERSTATE GAS COMPA
Address: PO BOX 1087
COLORADO SPRINGS, CO 80944

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4730		#156 81
COND	13.38	154		
PROD	5.5	4824	0	WITH 1025 SX CMT
SURF	9.625	77		
SURF	8.625	1415		WITH 750 SX CMT

Well Type: -GS GWI UIC Docket No: S017.9 Date/Time to Plug: 12/12/2005 9:00 AM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: CHRIS Company: EAGLE WELL SERVICE Phone: (620) 624-1904

Proposed Plugging Method: SPOT 25 SX CMT ON TOP OF EXISTING CIBP @ 4730'. TAG TOC. 50 SX CMT AT 1450'. 80 SX CMT FROM 690' TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/16/2005 1:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

SET CIBP @ 4730'. 1ST PLUG AT 1475' WITH 50 SX CMT. 2ND PLUG WITH 100 SX CMT FROM 700' TO SURFACE. ALL PLUGS INSIDE 5 1/2" CASING. PUMP 30 SX CMT DOWN BACKSIDE. PRESSURED TO 500# AND SHUT IN.

Perfs:


Top	Bot	Thru	Comments
4785	4793		
4758	4770		

RECEIVED
JAN 04 2006
KCC WICHITA

Remarks: USED COMMON CEMENT BY EAGLE WELL SERVICE.

Plugged through: TBG

District: 01



Signed

Jim Holland (TECHNICIAN)
PART II

INVOICED

DATE

1-4-06

INV. NO.

2006060944

Form CP-2