

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20474-00-00
Spot: W2NENW Sec/Twnshp/Rge: 25-29S-33W
4620 feet from S Section Line, 3400 feet from E Section Line
Lease Name: DANIELS Well #: 6-25
County: HASKELL Total Vertical Depth: 4675 feet

Operator License No.: 33578
Op Name: R J PATRICK OPERATING, LLC
Address: PO BOX 1157
LIBERAL, KS 67905

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	16	40		WITH GROUT
PROD	4.5	4660	2511	WITH 125 SX CMT
SURF	8.625	1646		WITH 625 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/29/2005 1:00 PM

Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.

Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 100# HULLS & 25 SX CMT. PLUG AT 1650' WITH 50 SX CMT. PLUG AT 650' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 11/30/2005 5:00 PM

KCC Agent: JIM HOLLAND

Actual Plugging Report:

PUMP 100# HULLS WITH 25 SX CMT. DISPLACE TO BOTTOM WITH MUD. PRESSURE TO 500# & SHUT IN. SDON. 1ST PLUG PULL OUT OF HOLE TO 1650'. CIRCULATE HOLE & PUMP 50 SX CMT. 2ND PLUG AT 650' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4660	4666	OH	

RECEIVED
JAN 03 2006
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01



Signed

Jim Holland PIRT II
(TECHNICIAN)

INVOICED

DATE

1-4-06

INV. NO

2006060946