

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-24095-00-00  
Spot: SWNWNW Sec/Twnshp/Rge: 8-34S-11E  
4161 feet from S Section Line, 4980 feet from E Section Line  
Lease Name: BETTY CASEMENT Well #: 1  
County: CHAUTAUQUA Total Vertical Depth: 1376 feet

Operator License No.: 7644  
Op Name: MILLER, BOBBY ELZO  
Address: 2061 INDEPENDENCE RD, UNIT 23  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1380	0	
SURF	7	40	0	

72  
#44

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/14/2005 8:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S INC.  
Proposal Rcvd. from: JOHN ELMORE Company: ELMORES, INC. Phone: (620) 249-2519

Proposed Plugging Method: TO PUMP CEMENT & GEL FOR BOTTOM & TOP PLUGS.

Plugging Proposal Received By: RON ROWE WitnessType: PARTIAL  
Date/Time Plugging Completed: 12/14/2005 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

BULLHEAD PUMPED 10 SACKS CEMENT DOWN 4.5" CASING FOR BOTTOM PLUG AT TD, THEN GEL SPACER & PRESSURED UP TO 600#. RAN 1" SPOOL HOSE INSIDE 4.5" CASING TO 350' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED SPOOL HOSE & TOPPED-OFF WELL. USED TOTAL OF 50 SACKS CEMENT & 2 SACKS GEL.

RECEIVED  
KCC DISTRICT #3  
DEC 27 2005 RR  
CHANUTE, KS

Perfs:

Top	Bot	Thru	Comments
1312	1328		

RECEIVED  
JAN 03 2006  
KCC WICHITA

Remarks: PLUGGED OLD OIL WELL.  
Plugged through: CSG

District: 03

Signed: [Signature]  
(TECHNICIAN)

INVOICED  
DATE 1-3-06  
INV. NO 2006060934