

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-25294-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 8-34S-11E
5115 feet from S Section Line, 4785 feet from E Section Line
Lease Name: CASEMENT, BETTY Well #: 6
County: CHAUTAUQUA Total Vertical Depth: 1361 feet

Operator License No.: 7644
Op Name: MILLER, BOBBY ELZO
Address: 2061 INDEPENDENCE RD, UNIT 23
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1361	0	
SURF	7	40	0	

44²³

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/16/2005 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S INC.
Proposal Rcvd. from: JOHN ELMORE Company: ELMORES, INC. Phone: (620) 249-2519

Proposed Plugging Method: TO PUMP CEMENT & GEL FOR BOTTOM & TOP PLUGS.

Plugging Proposal Received By: RON ROWE WitnessType: PARTIAL
Date/Time Plugging Completed: 12/16/2005 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

BULLHEAD PUMPED 10 SACKS CEMENT DOWN 4.5" CASING FOR BOTTOM PLUG, THEN GEL SPACER & PRESSURED TO 600#. RAN 1" SPOOL HOSE INSIDE 4.5" CASING TO 350' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED SPOOL HOSE & TOPPED-OFF WELL USED TOTAL OF 50 SACKS CEMENT & 2 SACKS GEL.

Perfs:

Top	Bot	Thru	Comments
1283	1314		

RECEIVED
KCC DISTRICT #3

DEC 27 2005 RR

CHANUTE, KS

RECEIVED

JAN 03 2006

KCC WICHITA

Remarks: PLUGGED OLD OIL WELL.

Plugged through: CSG

District: 03

Signed

(TECHNICIAN)

INVOICED

DATE

1-3-06

INV. NO

2006060934