

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21530-00-00
Spot: NENWSE Sec/Twnshp/Rge: 1-31S-8W
2310 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MCINTIRE Well #: 2
County: HARPER Total Vertical Depth: 4437 feet

Operator License No.: 6236
Op Name: M.T.M. PETROLEUM
Address: PO BOX 82
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	208		200 SX CMT

#144²⁰

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/01/2005 8:00 AM
Plug Co. License No.: 33610 Plug Co. Name: FOSSIL DRILLING, INC.
Proposal Rcvd. from: BRIAN SIROKY Company: FOSSIL DRILLING, INC. Phone: (620) 770-0621

Proposed Plugging Method: 35 sxs @ 1300'; 35 sxs @ 900'; 35 sxs @ 250'; 25 sxs @ 60'; and 15 sxs in rathole.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 10/01/2005 9:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The drill pipe was run open ended to 1300' and 35 sacks of cement was spotted in place. The drill pipe was pulled to 900' and 35 sacks of cement was spotted. The drill pipe was pulled to 250' and 35 sacks of cement was spotted. The drill pipe was pulled to 60' and 25 sacks of cement was circulated to surface. The rathole was circulated with 15 sacks of cement.

60/40 posmix with 4% gel

Acid Services

Perfs:

RECEIVED
KCC DISTRICT #2
DEC 15 2005
WICHITA, KS

RECEIVED
JAN 03 2006
KCC WICHITA

Remarks:

Plugged through: DP

District: 02

Signed _____

(TECHNICIAN)

INVOICED

DATE

1-3-06

INV NO

2006060933