

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-01508-00-01
Spot: SE NSWSE Sec/Twnshp/Rge: 27-29S-7W
1700 feet from S Section Line, 1659 feet from E Section Line
Lease Name: VORAN C Well #: 3
County: KINGMAN Total Vertical Depth: 5004 feet

Operator License No.: 32215
Op Name: RAKESTRAW BROS., L.L.C
Address: 4566 N.E. PARALLEL RD.
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4646		
SURF	8.625	403		

#162⁶³

Well Type: SWD UIC Docket No: D07924.0 Date/Time to Plug: 11/30/2005 8:30 AM
Plug Co. License No.: 32453 Plug Co. Name: ACID SERVICES LLC
Proposal Rcvd. from: CURT RAKESTRAW Company: RAKESTRAW BROTHERS Phone: (316) 644-2713

Proposed Plugging Method: 2-3/8" lined tubing cemented in hole. Open hole completed 4646'-5004'. Tubing set at 4606' and cement to surface with 500 sacks of Howco-Lite. Plugging orders are: pump 30 sacks of cement into open hole; leave 50'-100' of cement in pipe; perforate and squeeze cement into perforations; and circulate cement to surface.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/30/2005 3:45 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Dug out wellhead and found cement in braden head. Was not able to circulate the top plug. Pumped 30 sacks of cement. Plugged down tubing to plug open hole. Disp to within 100' of bottom of casing. S.I. Waited on cement to set. Shot perforation holes at 1250'. Tied onto tubing and pressured up to 400 lbs. Went back in with perforation gun to 750' holes. Tied on pump truck and got injection rate at 1.5 bbls/min at 0 pressure. Began pumping cement and got circulation to surface. Pumped cement until it returned to surface.

Acid Services
Common with 3% CACI

Perfs:

RECEIVED
KCC DISTRICT #2
DEC 14 2005
WICHITA, KS


RECEIVED
JAN 03 2006
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

INVOICED
DATE 1-3-06
INV. NO. 2006060936