

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-131-20190-00-00
Spot: NENENW Sec/Twnshp/Rge: 14-4S-14E
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: MCCLAIN Well #: 3-14 SWD
County: NEMAHA Total Vertical Depth: 4090 feet

Operator License No.: 33233
Op Name: HEARTLAND OIL & GAS, INC.
Address: 1610 INDUSTRIAL PARK DRIVE
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3965		445 SX CMT
SURF	8.625	281		130 SX CMT
T1	2.875	3942		

132 93

Well Type: SWD UIC Docket No: D28326.0 Date/Time to Plug: 12/01/2005 11:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE LITTELL Company: HEARTLAND OIL & GAS, INC. Phone: (913) 294-1400

Proposed
Plugging
Method:

GEL FROM 2919' TO 4135' CEMENT FROM 4135' TO 2915' GEL FROM 2915' TO 300' FROM 300' TO SURFACE.

Plugging Proposal Received By: TAYLOR HERMAN WitnessType: NONE
Date/Time Plugging Completed: 12/02/2005 12:00 PM KCC Agent: TAYLOR HERMAN

Actual Plugging Report:

Spotted 50 sacks of cement and 2 sacks of cottonseed hulls at bottom. Tagged cement at 3878 feet. Pumped gel from 3865 feet to 300 feet. Circulated 35 sacks of cement from 292 feet to surface.

Perfs:

Top	Bot	Thru	Comments
3965	4085		

RECEIVED
JAN 03 2006
KCC WICHITA

RECEIVED
KCC DISTRICT #3
DEC 21 2005 TCH
CHANUTE, KS

Remarks:

Plugged through: TBG

District: 03

Signed

Taylor C. Herman

(TECHNICIAN)

INVOICED

DATE 1-3-06

INV. NO 2006060932