

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-19536-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 33-25S-4E
381 feet from S Section Line, 5084 feet from E Section Line
Lease Name: EDMISTON Well #: 3
County: BUTLER Total Vertical Depth: 2517 feet

Operator License No.: 5420
Op Name: WHITE & ELLIS DRILLING, INC.
Address: PO BOX 48848
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	2172	0	20 SX CMT
SURF	10	155	0	3 YRDS TRANSIT MIX

81 80

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/11/2005 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: DALLAS FLOWERS Company: FLOWERS PRODUCTION Phone: (316) 321-0550

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/11/2005 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

10/11/2005 -- Sanded back to 1975'. RIH with tubing to 1960' and spotted 25 sacks of class 'A' cement. RIH with tubing between 7" and 10" to 251' and pumped 125 sacks of 60/40 posmix with 4% gel to surface. RIH inside 7" to 271' and pumped 56 sacks of cement to surface. Tagged cement at 55' inside 7" and 10" on backside of 7".
10/17/2005 -- Topped plug with 14 sacks of 60/40 posmix with 4% gel to surface.
United Cementing #6546

Perfs:

RECEIVED
KCC DISTRICT #2
DEC 15 2005
WICHITA, KS

RECEIVED
JAN 03 2006
KCC WICHITA

Remarks:
Plugged through: TBG

District: 02

Signed Duane R. Krueger
(TECHNICIAN)

INVOICED
DATE 1-3-06
INV. NO. 2006060938