

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-21161-00-00  
Spot: N2NENW Sec/Twnshp/Rge: 16-25S-5E  
5065 feet from S Section Line, 3262 feet from E Section Line  
Lease Name: ROBISON Well #: 1  
County: BUTLER Total Vertical Depth: 2625 feet

Operator License No.: 5420  
Op Name: WHITE & ELLIS DRILLING, INC.  
Address: PO BOX 48848  
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2617	0	100 SX CMT
SURF	8.625	203	0	130 SX CMT

31  
\$ 85

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/05/2005 8:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: DALLAS FLOWERS Company: FLOWERS PRODUCTION Phone: (316) 321-0550

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE  
Date/Time Plugging Completed: 10/06/2005 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

10/5/2005 -- Sanded back to 2400' and dumped bailed with 6 sacks of cement on top. Set rubber plug at 300'. RIH with 1" on backside to 271'. Pumped 56 sacks of 60/40 posmix with 4% gel to surface. RIH inside 5-1/2" casing at 300'. Pumped 49 sacks of 60/40 posmix with 4% gel to surface.

10/6/2005 -- Plugged down.

United Cementing #6541

Perfs:

Top	Bot	Thru	Comments
2486	2500		
2472	2486		
2458	2472		

RECEIVED  
KCC DISTRICT #2  
DEC 15 2005  
WICHITA, KS

RECEIVED  
JAN 03 2005  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger  
(TECHNICIAN)

INVOICED

DATE

1-3-06

INV. NO.

2006060938