

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-22399-00-00  
Spot: SESE Sec/Twnshp/Rge: 19-25S-5E  
988 feet from S Section Line, 725 feet from E Section Line  
Lease Name: WRIGHT Well #: 8  
County: BUTLER Total Vertical Depth: 2484 feet

Operator License No.: 5420  
Op Name: WHITE & ELLIS DRILLING, INC.  
Address: PO BOX 48848  
WICHITA, KS 67201

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2483	0	150 SX CMT
SURF	8.625	211	0	100 SX CMT

13  
# 80

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/10/2005 8:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: DALLAS FLOWERS Company: FLOWERS PRODUCTION Phone: (316) 321-0550

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE  
Date/Time Plugging Completed: 10/10/2005 5:00 PM KCC Agent: DUANE KRUEGER

**Actual Plugging Report:**

10/10/2005 -- RIH with tubing at 2465' and spotted 25 sacks of class 'A' cement. Waited 2 hours and tagged at 2267'. Shot 5-1/2" casing at 312' and pumped 149 sacks of 60/40 posmix with 4% gel to surface. Left 5-1/2" casing in hole. Tagged cement at 30' and topped plug with 6 sacks of cement to surface.

United Cementing #6545

**Perfs:**

Top	Bot	Thru	Comments
2482	2484		

**RECEIVED  
KCC DISTRICT #2  
DEC 15 2005  
WICHITA, KS**


**RECEIVED  
JAN 03 2006  
KCC WICHITA**

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

**INVOICED**  
DATE 1-3-06  
# 2006060938