

"AMENDED"  
01/06/2006

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-25451-00-00  
Spot: NWSWSE Sec/Twnshp/Rge: 22-14S-20W  
930 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: HELEN Well #: 22-1  
County: ELLIS Total Vertical Depth: 3854 feet

Operator License No.: 33335

Op Name: IA OPERATING, INC.

Address: 900 N TYLER ROAD #14  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	235	0	165 SX CMT

Well Type: DH

UIC Docket No:

Date/Time to Plug: 09/07/2005 9:00 AM

Plug Co. License No.: 30606

Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: ANDY DINKEL

Company: MURFIN DRILLING CO., INC.

Phone: (316) 267-3241

Proposed Plugging Method: Order 100 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Keith Kingsley, landowner, under 82-3-119 made arrangements with operator to use wellbore down to 600' to run water well casing and complete for a Dakota domestic water well. Plugging plan modified to meet landowner request.

01/06/2006 - Landowner decided to abandon efforts to convert to waterwell.  
Decided to P&A.

Plugging Proposal Received By: HERB DEINES

WitnessType: NONE

Date/Time Plugging Completed: 09/07/2005 12:00 PM

KCC Agent: HERB DEINES

Actual Plugging Report:

Perfs:

1st. Plug at 3750' w/25 sxs.  
2nd. Plug at 1450' w/25 sxs.  
3rd. Plug at 800' w/25 sxs.  
Drill pipe pulled to 600' and hole circulated with clean drilling mud.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

01/06/2006 - Ran tubing in hole - tagged cement at 235'.  
Allied pumped 40 sxs.  
Pulled to 60' and pumped 20 sxs cwc.  
(11:00 AM)

RECEIVED  
JAN 12 2006  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

*MD*

Signed

*Richard Williams*

(TECHNICIAN)