

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20895-00-01
Spot: SENESW Sec/Twnshp/Rge: 9-12S-15W
1650 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SUTTON B Well #: 9
County: RUSSELL Total Vertical Depth: 2496 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 740, LB 30
DALLAS, TX 75205

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2500	0	150 SX CMT
SURF	8.625	730	0	UNKNOWN

#81 12 ✓

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/21/2005 12:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. Phone: (214) 219-8883

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/21/2005 3:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Tied onto casing and pumped 160 sxs 60/40 pozmix - 10% gel cement with 800# hulls.
Max. P.S.I. 1000#. S.I.P. 1000#.
Pressured backside to 650# P.S.I. Held.

Perfs:

Top	Bot	Thru	Comments
2390	2394		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Case Morris
(TECHNICIAN)

HD

INVOICED
DATE 1-09-06
INV. NO 2006060955

RECEIVED
JAN 09 2006
KCC WICHITA

Form CP-2/3

DEC 29 2005

MAI OPERATIONS
 P.O. BOX 33, RUSSELL, KS. #9 SUTTON "B" "OWWO" 9-12-15W
 SE NE SW

CONTR DUKE DRILLING, INC. CITY RUSSELL

GEOL _____ FIELD FAIRPORT

E 1731 KB CM 5/29/76 CARD ISSUED 6/23/76 IP P 50 BOPD + WTR
 TARK 2390-94

	+	+	+
	-	-	-

API 15-167-20,895

	TOPS	DEPTH	DATUM
ANH		775	+ 956
TOP		2609	- 878
HEEB		2830	-1099
TOR		2850	-1119
LKC		2880	-1149
ARB		3180	-1449
RTD		3188	-1457
NEW TOP:			
TARKIO		2381	- 650

OLD INFO: OPERATOR WAS REEL-HARDMAN #2
 SUTTON, SPD 5/22/58, 8 5/8" 730, 5 1/2" 3181
 MICT - DD 3188 NS, PB 3176, PF 24/3164
 -75, A 500, REC WTR, PB 3000, 24/2924-
 29, A 1000 REC WTR, PB 2916, 25/2905-10,
 A 1500, REC WTR, PB 2896, 24/2848-54,
 AC 1000 REC WTR

NEW INFO: RE-ENTERED 5/29/76, CO & SET
 5 1/2" CSG @ 2499/150SX
 MICT - PF TARKIO SD 2390-94, FRAC 512
 BGW + 12,500 SD, REC LD + SWB 25 BFPH,
 POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS