

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20464-00-00
Spot: SWNE Sec/Twnshp/Rge: 16-13S-22W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease Name: HARVEY Well #: 1
County: TREGO Total Vertical Depth: 4242 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3990		
PROD	4.5	4241	0	175 SX CMT
SURF	8.625	270	0	170 SX CMT

87
#137

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/03/2006 12:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 225 sxs 60/40 pozmix - 10% gel - 400# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: PARTIAL
Date/Time Plugging Completed: 01/03/2006 3:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3795' and topped with 5 sxs using a dump bailer.
Cut casing free at 2000'.
Pulled up to 1750' and pumped 80 sxs cement with 300# hulls.
Pulled up to 850' and spotted 40 sxs cement with 100# hulls.
Pulled up to 200' and circulated cement with 85 sxs.
POOH. Hole full of cement.

Perfs:

Top	Bot	Thru	Comments
4103	4106		
3843	3849		


Remarks: COPELAND ACID & CEMENTING.

Plugged through: CSG

INVOICED
DATE 1-9-06
SER. NO. 2006060953

District: 04

Signed



(TECHNICIAN)

RECEIVED

JAN 09 2006

KCC WICHITA

Form CP-2/3

JAN 06 2006

RAINS & WELLS OIL CO., INC.

435 PAGE COURT, 2211 W. DOUGLAS #1 HARVEY
WICHITA, KS.

16-13-22W
C SW NE

CONTR CO. TOOLS


CITY IRLGO

GEOL HARLAN DIXON

FIELD WC (1 1/2 W OF HOLLAND)

E 2271 KB CM 4/4/78 CARD ISSUED 5/11/78 IP P 90 BOLD, NW

LANS 3843-49



API 15-195-20,464

LOG	TOPS	DEPTH	DATUM
ANH	1745	+ 526	
B ANH	1791	+ 480	
HEEB	3620	-1349	
LANS	3656	-1385	
BKC	3902	-1631	
PAWN	4009	-1738	
LABETTE SH	4058	-1787	
OSAGE	4165	-1894	
GILMORE CITY	4220	-1949	
LTD	4242	-1971	
RTD	4245	-1974	

8-5/8" 242/170sx, 4 1/2" 4241/175sx
 DST (1) 3690-3730/30-30-30-30, E 1'M,
 SIP 401-327#, FP 53-53#, BHT
 114"
 DST (2) 3730-55/30-30-90-60, 72'
 HOOM, 124' MO, 62' SMO, 240' SOCSW
 SIP 1245-1245#, FP 84-116#, 148-
 264#, HP 1985-1964#
 DST (3) 3811-3840/30-30-30-30, 10'M
 ALL PRESSURES 42#, HP 1996-
 1975#, BHT 112"
 DST (4) 3848-60/PER FAILED
 DST (5) 3848-60/30-30-90-60, CTS/
 3'10", 2765' GO, SIP 1181-1160#
 FP 116-453#, 465-396#, HP 1942-
 1911# (OVER)

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

16-13-22W
 C SW NE

HARLAN DIXON