

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20526-00-00
Spot: S2NWNE Sec/Twnshp/Rge: 16-13S-22W
4290 feet from S Section Line, 1980 feet from E Section Line
Lease Name: HARVEY Well #: 2
County: TREGO Total Vertical Depth: 4220 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, INC.
Address: PO BOX 438
HAYSVILLE, KS 67060

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|------------|
| PROD | 4.5 | 4224 | 0 | 175 SX CMT |
| SURF | 8.625 | 206 | 0 | 150 SX CMT |

4137.85

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/29/2005 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 300# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/29/2005 1:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3800' and topped with 5 sxs cement using a dump bailer.
Cut casing free at 1250'.
Pulled up to 1200' - spotted 60 sxs cement with 200# hulls.
Pulled up to 500' - spotted 25 sxs cement with 100# hulls.
Pulled up to 200' and circulated cement with 75 sxs.
POOH. Hole full of cement.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3847 | 3852 | | |

RECEIVED
JAN 06 2006
KCC WICHITA

INVOICED

Remarks: COPELAND ACID & CEMENTING.

Plugged through: CSG

DATE 1-9-06
INV. NO. 2006060953

District: 04

Signed Jay Pfeifer
(TECHNICIAN)

DEC 30 2005

RAINS & WILLIAMSON OIL CO.
 435 BAGE COURT 22, W. DOUGLAS #2 HARVEY
 WICHITA, KS. 67202
 CONTR RAINS & WILLIAMSON OIL CTY TREGO

16-13-22W
 C S/2 NW NE

GEOL _____ FIELD HOLLAND NW CONF

E 2278 KB CM 3/2/79 CARD ISSUED 8/4/79 IP P 60 BOPD
LANS 3847-52

| | |
|---|---|
| + | + |
| + | + |

API 15-195-20,526

| LOG | TOPS | DEPTH | DATUM |
|--------------|------|-------|-------|
| *ANH | | 1746 | + 532 |
| *B ANH | | 1795 | + 485 |
| HEEB | | 3624 | -1346 |
| TOR | | 3640 | -1362 |
| LANS | | 3658 | -1380 |
| BKC | | 3910 | -1632 |
| PAW | | 4020 | -1742 |
| LAB | | 4069 | -1791 |
| FT SC | | 4095 | -1817 |
| CHER SD | | 4110 | -1832 |
| MISS | | 4195 | -1917 |
| LTD | | 4220 | -1942 |
| RTD | | 4225 | -1947 |
| *SAMPLE TOPS | | | |
| | | | |

8-5/8" 206/150sx, 4 1/2" 4224/175sx
 DST (1) 3691-3735/30-30-30-30, REC
 10' M, W/SPKS 0, SIP 114-52#, FP
 41-41/41-41#
 DST (2) 3734-3750/30-30-30-30, REC 15'
 M, SIP 1151-1068#, FP 52-52/52-52#
 DST (3) 3841-3870/30-60-60-60, 800' GI
 REC 400' VHOCM, 40' VSMCO, 125'
 MDY 0, SIP 510-479#, FP 52-73/114-
 135#
 MICT - CO, PF 3847-52, AC 500 GAL, SWB
 TST 36 BO/3HRS, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS