

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-22170-00-00  
Spot: SENE Sec/Twnshp/Rge: 14-26S-14W  
940 feet from N Section Line, 330 feet from E Section Line  
Lease Name: MOORE Well #: 1  
County: PRATT Total Vertical Depth: 4375 feet

Operator License No.: 31980  
Op Name: LOTUS OPERATING COMPANY, L.L.C.  
Address: 100 S. MAIN, STE 420  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4360	2160	WITH 200 SX CMT
SURF	10.75	305		WITH 250 SX CMT

\$142<sup>19</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/27/2005 3:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MARIO MARTINEZ Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND OFF TO 3780' WITH 4 SX CMT. 10 SX GEL & 50 SX CMT AT 1000'. 50 SX CMT AT 330'. 10 SX CMT AT 40'.

Plugging Proposal Received By: JIM HOLLAND WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/27/2005 4:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 3780' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUG DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 1000' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4230	4250		
4186	4192		
3836	3841		

RECEIVED  
KANSAS CORPORATION COMMISSION  
JAN 11 2006  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: CSG

District: 01



Signed

*Stephen J. Pfeifer*  
(TECHNICIAN)

INVOICED

DATE 1-11-06  
INV. NO. 2006060958

Form CP-2/3