

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-189-21593-00-00  
Spot: SESE Sec/Twnshp/Rge: 18-31S-38W  
660 feet from S Section Line, 660 feet from E Section Line  
Lease Name: KANCO PROPERTIES Well #: 1  
County: STEVENS Total Vertical Depth: 6100 feet

Operator License No.: 6113  
Op Name: LANDMARK RESOURCES, INC.  
Address: 1616 S. VOSS, SUITE 150  
HOUSTON, TX 77056

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2255		WITH 2 SX CMT
CIBP		5590		WITH 2 SX CMT #198 <sup>25</sup>
PC		3000		
PROD	5.5	6099	1560	WITH 225 SX CMT
SURF	8.625	1708		WITH 605 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/19/2005 8:00 AM  
Plug Co. License No.: 99989 Plug Co. Name: PLAINS WELL SERVICE  
Proposal Rcvd. from: ALAN WALKER Company: LANDMARK RESOURCES Phone: (316) 683-8080

Proposed Plugging Method: CIBP @ 5600' WITH 2 SX CMT. CIBP @ 2250' WITH 2 SX CMT. PLUG AT 1740' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/19/2005 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

HOLES IN CASING AT 2100' & BETWEEN 5150' & 3000'. SHOT PIPE AT 1696'. DROPPED 3 JOINTS OF PIPE IN THE HOLE. 1ST PLUG SET CIBP @ 5590' WITH 2 SX CMT. 2ND PLUG SET CIBP @ 2255' WITH 2 SX CMT. 3RD PLUG RUN 2 3/8" TUBING TO 1757' & PUMP 15 SX GEL & 50 SX CMT. 4TH PLUG PULL TUBING TO 600' & PUMP 40 SX CMT. 5TH PLUG PULL TUBING TO 60' & CIRCULATE 20 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
5664	5682		

RECEIVED  
JAN 11 2006  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL & COMMON CMT BY ALLIED.

Plugged through: TBG

District: 01



Signed

Ken Jehlik  
(TECHNICIAN)  
INVOICED  
DATE 1-11-06  
INV. NO 2006060964