

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-21167-00-01
Spot: SWNWSE Sec/Twnshp/Rge: 24-33S-11E
1609 feet from S Section Line, 2063 feet from E Section Line
Lease Name: L D S CHURCH Well #: 4
County: CHAUTAUQUA Total Vertical Depth: 1243 feet

Operator License No.: 6321
Op Name: MCCANN DRILLING, INC.
Address: 511 N CHAUTAUQUA
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1243	0	
SURF	7	300	0	

#40 40

Well Type: EOR UIC Docket No: E24898.2 Date/Time to Plug: 08/29/2005 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S INC.
Proposal Rcvd. from: JOHN ELMORE Company: ELMORES, INC. Phone: (620) 249-2519

Proposed Plugging Method: TO RUN 1" TO TD & PUMP GEL & CEMENT FOR BOTTOM & TOP PLUG.

Plugging Proposal Received By: RON ROWE WitnessType: PARTIAL
Date/Time Plugging Completed: 08/29/2005 5:00 PM KCC Agent: RON ROWE

Actual Plugging Report:

RAN 1" HYDRIL INSIDE 4.5" CASING TO 1242' & GELLED HOLE, THEN PUMPED 10 SACKS CEMENT FOR BOTTOM PLUG. PULLED 1" & PERFORATED 4.5" @ 350'. RAN 1" BACK IN 4.5" TO 350' & PUMPED/CIRCULATED CEMENT TO SURFACE. PULLED 1" & TOPPED-OFF WELL. USED TOTAL OF 60 SACKS CEMENT & 2 SACKS GEL.

Perfs:

Top	Bot	Thru	Comments
1206	1224		

RECEIVED
KCC DISTRICT #3
AUG 30 2005
CHANUTE, KS

RECEIVED
DEC 09 2005
KCC WICHITA

Remarks: PLUGGED OLD UIC WELL THAT HAD FAILED MIT.

Plugged through: TBG

District: 03

Signed [Signature]
(TECHNICIAN)

INVOICED
DATE 12-9-05
INV. NO 2006060842