

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21494-00-01
Spot: NESWSWNW Sec/Twnshp/Rge: 4-29S-15W
2280 feet from N Section Line, 630 feet from W Section Line
Lease Name: BOSLER Well #: 4
County: PRATT Total Vertical Depth: 4880 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S. MAIN, STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4878	2730	WITH 350 SX CMT
SURF	8.625	431		WITH 300 SX CMT <i>#158</i>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/04/2006 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MARIO MARTINEZ Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND BACK TO 4650' & 5 SX CMT. PLUG AT 950' WITH 10 SX GEL & 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/04/2006 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SAND BACK TO 4650' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 950' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4738	4750		
4708	4718		

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 11 2006
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.
Plugged through: CSG

District: 01

RECEIVED
JAN 10 2006
KCC Dodge City

Signed Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
DATE 1-11-06
T.V. NO. 2006060958

Form CR-2/3