

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

Well Plugging Record  
K.A.R. -82-3-117

API NUMBER 15-097-2070200-01  
LEASE NAME 15-095-20702-00.01  
WELL NUMBER Leiss GU 'A'  
2-12 OWWO

TYPE OR PRINT  
NOTICE: Fill out completely and return  
to Cons. Div. office within 30 days.

1980 Ft. from South Line of Section  
660 Ft. from West Line of Section

LEASE OPERATOR McCoy Petroleum Corporation SPOT LOCATION NW SW  
ADDRESS 8080 E. Central Section 12 Township 27s Range 18w  
CITY, STATE, ZIP Wichita, Kansas 67206 County Kiowa  
PHONE # 316-636-2737 Date Well Completed 12/21/05  
Character of Well Dry and Abandoned Date Plugging Commenced 12/21/05  
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 12/21/05

The plugging proposal was approved on December 20, 2005 (date)  
by Mike Maier (KCC District Agent's Name)

Is ACO-1 Filed? ? If not, is well log attached? Yes  
Producing Formation(s) D&A Depth to Top Bottom T.D. 908

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT         | FROM | TO  | SIZE | PUT IN | PULL OUT |
|-----------|-----------------|------|-----|------|--------|----------|
| Redbeds   | Shale/Siltstone | 472  | 908 |      |        |          |
|           |                 |      |     |      |        |          |
|           |                 |      |     |      |        |          |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.

Plugged well on 12/20/05 in this manner: Heavy mud in hole and between all plugs. Used 135 sx of  
of 60/40 Poz, '6% Gel. Bottom plug at 840' - 40 sx, 2nd plug at 400' - 50 sx and top plug at 60' - 20 sx.

Rathole - 15 sx and mousehole-10 sx. Job completed at 3:30 pm on 12/20/05. Acid services ticket #11421.

Plugging orders from Mike Maier on 12/20/05. Sterling reported plugging to KCC on 12/21/05.

Name of Plugging Contractor Sterling Drilling Company  
Licence No. 5142  
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124  
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation (Operator)

STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well,  
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of  
the above described well as filed that the same are true and correct, so help me God.


(Signature) Gary M. Talbott  
(Gary Talbott, Vice-President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 29th day of December, 2005

RECEIVED  
DEC 30 2005  
KCC WICHITA

Pamela S. Fields  
(Notary Public)



My Commission Expires:

Form CP-4  
Revised 12-92

*am*

# Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006  
Office Phone (620) 672-9508, Fax 672-9509

## SAMPLE LOG

Leiss GU 'A' 2-12 OWWO

LOCATION: NW SW  
API: 15-095-20702-00.01

Section 12 T 27s R 18w  
Kiowa County, Kansas

OWNER: McCoy Petroleum Corporation  
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 19-Dec-05  
COMPLETED: 20-Dec-05

TOTAL DEPTH: DRILLER 908 FEET  
LOGGER No Log FEET

Ground Elevation: 2153  
KB Elevation: 2162

## LOG

10' to 45' Open hole  
40' to 95' Hard Cement  
95' to 305' Open hole  
305' to 360' Hard Cement  
360' to 472' Hard Cement (Drilling fluid clear water w/ no color)  
472' to 908' Drilling fluid turned red (Drilling new hole)

## CASING RECORDS

### Surface Casing Data:

Existing 8-5/8" casing set at 352'. Plugged on 12/01/80 by Cinco Exploration. Plugs are :  
10 sks at 40', 30sxx and plug at 350' and 50 sks at 550'. Heavy mud to 4830'.

### Plugging Data:

Plugged well on 12/20/05 in this manner: Heavy mud in hole and between all plugs. Used 135 sx of  
of 60/40 Poz, '6% Gel. Bottom plug at 840' - 40 sx, 2nd plug at 400' - 50 sx and top plug at 60' - 20 sx.  
Rathole - 15 sx and mousehole-10 sx. Job completed at 3:30 pm on 12/20/05. Acid services ticket #11421.  
Plugging orders from Mike Maier on 12/20/05. Sterling reported plugging to KCC on 12/21/05.

## DEVIATION SURVEYS

None Taken

RECEIVED  
DEC 30 2005  
KCC WICHITA