

STATE OF KANSAS
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
130 South Market - Room 2078
Wichita, Kansas 67202

RECEIVED
JAN 05 2006
FORM 1 (3/92)
KCC WICHITA

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-159-20644-0001 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Hupfer Operating, Inc. KCC LICENSE # 30380
ADDRESS P.O. Box 216 (owner/company name) CITY Hays (operator's)

STATE KS ZIP CODE 67601 CONTACT PHONE # (785) 628-8666

LEASE Cross Reach Farms WELL# 2 SEC. 32 T. 19 R. 10 (~~East~~/West)

NE - NE - NW SPOT LOCATION/0000 COUNTY Rice

4950 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

2970 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL ___ GAS WELL X D&A ___ SWD/ENHR WELL ___ DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 7" SET AT 247 CEMENTED WITH 175 SACKS

PRODUCTION CASING SIZE 4½" SET AT 1489 CEMENTED WITH 50 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perf. 1439 to 1443

ELEVATION 1786 T.D. 1489 PBTD _____ ANHYDRITE DEPTH 1353
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD X POOR _____ CASING LEAK _____ JUNK IN HOLE _____
(Pull casing)

PROPOSED METHOD OF PLUGGING Sand off 50' above perforations @ 1389' & 5 sxs. cement on top. 35 sxs. cement @ 1300', 35 sxs. cement @ 900', 100 sxs. cement 300' to surface. Cement 60/40 poz 4% gel. Per district #2

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Mike Kelso/Dennis D. Hupfer PHONE# (785) 628-8666

ADDRESS P.O. Box 216 City/State Hays, KS 67601

PLUGGING CONTRACTOR Mike's Testing & Salvage, Inc. KCC LICENSE # 31529

ADDRESS P.O. Box 467, Chase, KS 67524 (company name) PHONE # (620) 938-2943 (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Feb. 1, 06

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1-02-06 AUTHORIZED OPERATOR/AGENT: _____

(signature)
Dennis D. Hupfer - President



KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Hupfer Operating, Inc.
PO Box 216
Hays, KS 67601-0216

January 12, 2006

Re: CROSS REACH FARMS #2
API 15-159-20644-00-01
NENENW 32-19S-10W, 4950 FSL 2970 FEL
RICE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

District: #2
3450 N. Rock Road, Suite 601
Wichita, KS 67226
(316) 630-4000

Sincerely



David P. Williams
Production Supervisor