

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-30047-00-01
Spot: N2SENV Sec/Twnshp/Rge: 30-19S-21W
1980 feet from N Section Line, 1980 feet from W Section Line
Lease Name: MOORE D OWWO Well #: 4
County: NESS Total Vertical Depth: 4436 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1300		
PROD	4.5	4435	0	WITH 100 SX CMT
SURF	8.625	506		WITH 200 SX CMT

\$144¹⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/21/2005 9:30 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OIL FIELD SERVICE, INC.
Proposal Rcvd. from: BENNIE Company: RITCHIE EXPLORATION Phone: (316) 691-9500

Proposed Plugging Method: RUN TUBING TO 4300' & SPOT 30 SX CMT WITH 150# HULLS. CIBP @ 1300' & PERFORATE AT 650'. PUMP 140 SX CMT TO SURFACE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/21/2005 1:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TUBING TO 4300'. SPOT 30 SX CMT WITH 150# HULLS. PULL TUBING. SET CIBP @ 1300'. PERFORATE AT 650'. PUMP 140 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4404	4424		

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 17 2006
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
DEC 30 2005
KCC Dodge City

Signed

Michael Maier
(TECHNICIAN)

INVOICED

DATE 1-17-06

WELL NO. 2006060979

Form CP-3/3

[Signature]