

*Corrected Copy*

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20384-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 22-10S-25W  
2310 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: BRUNGARDT A Well #: 4  
County: GRAHAM Total Vertical Depth: 4090 feet

Operator License No.: ~~5363~~ 5364  
Op Name: BEREXCO, INC. *Beren Corp.*  
Address: ~~PO BOX 20380~~ PO Box 20380  
WICHITA, KS 67208

PROD Size: 5.5 feet: 4090 w/125 sxs cmt  
SURF Size: 8.625 feet: 214 w/175 sxs cmt

*#13293*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/01/2004 8:00 AM  
Plug Co. License No.: 31720 Plug Co. Name: STEWART WELL SERVICE INC  
Proposal Rcvd. from: MARK LEIKER Company: BEREXCO, INC. Phone: (785) 628-6101

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 10% gel - 800# hulls.  
Planned to pull casing from 1000' to surface.  
CIBP at 3860' - 3883' - 3888'. Casing leaks.  
Squeeze at 1990' - 2010' - 2095' - 2300' - 3041' - 3069' w/250 sxs;  
3029' - 3057' w/50 sxs; 1515' - 1545' w/150 sxs; 3046' - 3078' w/200 sxs.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/01/2004 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH and tagged sand on bottom at 3650'.  
Pulled tubing to 3600' - pumped 60 sxs cement with 400# hulls mixed in.  
Pulled tubing to 2650'. Allied rigged to tubing and pumped 100 sxs 60/40 pozmix with 200 sxs hulls mixed in.  
Some fluids circulated out of casing near surface.  
Decided not to pull casing.  
Pulled tubing to 1350' - pumped 85 sxs cement with 200# hulls to circulate cement to surface.  
Pulled tubing and rigged up to 5 1/2" casing with a swedge. Pumped 20 sxs cement. S.I.P. 100#.  
Cement blew out of hole in casing near surface.  
Tied onto backside and pumped 110 sxs 60/40 pozmix.  
Max. P.S.I. 0#. S.I.P. 0#.  
Cement was near surface - will cut off and ready mix backside if needed.

Perfs:

Top	Bot	Thru	Comments
4004	4006		
3983	3990		
3962	3967		
3904	3906		
3865	3867		
3820	3826		
3041	3069		
3029	3037		
2010	2025		

RECEIVED  
JUN 03 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #5972.

Plugged through: TBG

District: 04

*10*

Signed *Patrick Stewart*  
(TECHNICIAN)

INVOICED

DATE 6-3-04  
INV. NO. 20040616-32

*Copy*  
Form CP-2/3  
*Rec'd July 1, 2004*

JUN 02 2004