

3 022716

15-207-19509-00-08

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20040041

NW SW, SW 1/4 Sec/Twp/Rge S.34-T.26S.-R.16E.

875 feet from south section line

4683 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: STATE OF KANSAS FeeFund

Name & FEE FUND PLUGGING

Address

AB oil well X Gas Well SWD Well/ Input Well

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE

Lic. # 6372

Address: BOX 386, RR4, CHANUTE, KANSAS 66720

Company to plug at: Hour: 9:30A.M. Day: 13 Month: 4 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 1000' THAT HAD
 BEEN CEMENTED IN AT T.D. ONLY. 1" PIPE HAD BEEN "LEFT HANDED" FROM THE WELL
 TO 525'. PROBABLY 1" PIPE REMAINS IN THE WELL FROM 525' TO NEAR T.D.. THE PLUGGING
 PROPOSAL IS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part TECHNICIAN None X

Operations Completed: Hour: 12:30P.M. Day: 13 Month: 4 2005

Actual Plugging Report: 3/4" PIPE WAS RAN INTO THE 2" CASING TO 525'. CEMENT

WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT

SURFACE. THE 3/4" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" & 6" ANNULUS

TO 300'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM

THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS

FILLED FROM SURFACE. 69 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO. 73) (THIS WELL WAS NO.10-I ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

RECEIVED

APR 28 2005

KCC WICHITA

I DID NOT observe this plugging.

Signed:


 TECHNICIAN

