

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-22416-00-00  
Spot: E2SESE Sec/Twnshp/Rge: 29-7S-22W  
630 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: DAVIS Well Number: 2  
County: GRAHAM Total Vertical Depth: 3910 feet

Operator License No.: 30076  
Op Name: A & A PRODUCTION  
Address: PO BOX 100  
HILL CITY, KS 67642

Conductor Pipe: Size feet:  
Surface Casing: Size 8.62 feet: 210 150 SX CMT  
Production: Size 5.5 feet: 3910 125 SX CMT \$127.08  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/02/2001 3:00 PM  
Plug Co. License No.: 30076 Plug Co. Name: A & A PRODUCTION  
Proposal Rcvd. from: ANDY ANDERSON Company: A & A PRODUCTION Phone: (785) 421-6266

Proposed Plugging Method: Order 8 yards Redi-Mix - 6 sxs common cement with sand/yard.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 05/02/2001 5:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 210' w/150 sxs cwc. 5 1/2" set at 3910' w/125 sxs.  
Two staged to surface.  
Fluid level low.  
Filled casing with 8 yards Redi-Mix.  
Prod. Perfs 3670' - 3693'.  
Plug complete.

INVOICED

DATE 5-29-01  
INV. NO. 2001061839

KANSAS CORPORATION COMMISSION  
5/22/01  
MAY 22 2001

CONSERVATION DIVISION

Remarks: SPOT LOCATION SHOULD READ 30'S.CE2SESE 29-07-22W.

Plugged through: CSG

District: 04

Signed Carl Goodrow  
(TECHNICIAN)

TD

MAY 10 2001

A & A DISCOVERY, INC  
HILL CITY, KS 67642

29-07 -22W  
30°S, C E/2 SE SE

#A-2 DAVIS

site: 2-1/2 N & 2-1/2 E OF HILL CITY, KS      city: GRAHAM      API 15-065-22416  
contr: WESTERN KANSAS DRILLING      field: HARMONY NO. EXT (1/8 NW)  
geol: PAT DEENIHAN

fr	spd	drig	card	last
date 10/15/87	date 10/20/87	comp 10/28/87	issued 02/03/88	revised 02/03/88


ELV: 2268 KB LOG

tops.....	depth/datum
ANH.....	1883 +385
B/ANH.....	1918 +350
TOP.....	3264 -996
HEEB.....	3471 -1203
TOR.....	3494 -1226
LANS.....	3510 -1242
STARK.....	3681 -1413
BKC.....	3708 -1440
ARB.....	3833 -1565
RTD.....	3910 -1642

IP status:

OIL, P 70 BO & 10 BWPD, LKC 3670-3693 OA,  
CSG: 8-5/8" 210 / 150 SX, 5-1/2" 3910 / 125 SX

NO CORES

DST (1) 3531-3556 (LKC), 30-30-30-30, REC 1200' MW  
ISIP 1027# FSIP 933# IFP 169# 370# FFP 476# -550#  
DST (2) 3665-3705 (LKC), 30-45-60-90, 60' GIP, REC  
150' MCO, 15' CLEAN OIL ISIP 1010# FSIP 1000# IFP  
158# -105#

NOTE: CORRECTION: 2/3/88 - ORIGINALLY FIRST  
REPORTED AS #2 DAVIS

(over)

COPYRIGHT 1988  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS