

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-171-20608-00-00
Spot: SENESEW Sec/Twnshp/Rge: 14-19S-34W
1700 feet from S Section Line, 2300 feet from W Section Line
Lease Name: SURF Well #: 350
County: SCOTT Total Vertical Depth: 4930 feet

Operator License No.: 31819
Op Name: CHOLLA PRODUCTION, L.L.C.
Address: 1641 CALIFORNIA ST., STE 300
DENVER, CO 80202

\$ 160²³

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 12/29/2005 3:00 AM
Plug Co. License No.: 33375 Plug Co. Name: CHEYENNE DRILLING, LP
Proposal Rcvd. from: ROGER PEARSON Company: _____ Phone: _____

Proposed Plugging Method: 1ST PLUG AT 2287' WITH 50 SX CMT. 2ND PLUG AT 1380' WITH 80 SX CMT. 3RD PLUG AT 710' WITH 50 SX CMT. 4TH PLUG AT 360' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: NONE
Date/Time Plugging Completed: 12/29/2005 6:00 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG AT 2287' WITH 50 SX CMT. 2ND PLUG AT 1380' WITH 80 SX CMT. 3RD PLUG AT 710' WITH 50 SX CMT. 4TH PLUG AT 360' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Perfs:

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 17 2006
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
JAN - 3 2006
KCC Dodge City

Signed

Steve Durrant
(TECHNICIAN)

INVOICED
DATE 1-17-06
INVOICE NO 2006060975