

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-207-21578-00-00
Spot: NWNESE Sec/Twnshp/Rge: 19-25S-14E
2310 feet from S Section Line, 810 feet from E Section Line
Lease Name: AKINS Well #: 32
County: WOODSON Total Vertical Depth: 1500 feet

Operator License No.: 30345
Op Name: PIQUA PETRO, INC.
Address: 1331 XYLAN ROAD
PIQUA, KS 66761

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1495	650	
SURF	7	40		

48⁷⁵

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/22/2005 9:30 AM
Plug Co. License No.: 32147 Plug Co. Name: K.E. SNYDER CO., LLC
Proposal Rcvd. from: ADDAM SPLECTER Company: PIQUA PETRO, INC Phone: (620) 468-2681

Proposed Plugging Method: THIS WELL CONSISTED OF 4 1/2" CASING TO 1495' THAT HAD BEEN CEMENTED IN AT T.D. ONLY WITH 50 SACKS OF CEMENT. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., TO SALVAGE AS MUCH OF THE CASING AS POSSIBLE, TO PLACE A 50' CEMENT PLUG AT 700', AND TO CIRCULATE THE WELL FULL OF CEMENT FROM 200' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: PARTIAL
Date/Time Plugging Completed: 12/28/2005 11:00 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

2" TUBING WAS RAN INTO THE WELL TO T.D., 15 SACKS OF CEMENT WERE PUMPED THROUGH THE 2" TO 1430'. THE 2" WAS REMOVED. AN EFFORT TO PART THE 4 1/2" CASING AT 1000' FAILED. THE 4 1/2" CASING WAS PARTED AT 650' AND 650' OF 4 1/2" CASING WAS REMOVED FROM THE WELL. A SOLID BRIDGE WAS BUILT AT 650'. THE WELL WAS GELLED FROM 650' TO SURFACE. 2" PIPE WAS RAN INTO THE WELL TO 650. 20 SACKS OF CEMENT WERE PUMPED AT 650'. THE 2" TUBING WAS PULLED TO 200'. CEMENT WAS PUMPED INTO THE 2" TUBING UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 2" WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 87 SACKS OF CEMENT TOTAL WERE PUMPED INTO THIS WELL.

RECEIVED
KCC DISTRICT #3

JAN 4 2006 CPT

CHANUTE, KS

Perfs:

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

RECEIVED
JAN 17 2006
KCC WICHITA

INVOICED
DATE 1-17-06
INV. NO. 2006060978

Form CP-2/3