


STATE OF KANSAS
STATE CORPORATION COMMISSION

15-065-60569-00-50

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Graham County. Sec 31 Twp. 7S Rge. 22W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW SE

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Jones "C" Well No. 1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 23, 1958

Application for plugging filed April 24, 1958

Application for plugging approved April 24, 1958

Plugging commenced May 2, 1958

Plugging completed May 2, 1958

Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius, Box 731, Hill City, Ks.

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3935 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT-IN	PULLED OUT
				8-5/8"	3-31-58	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sand to 3690', dumped 4 sacks
cement, mud to 200', set rock
bridge with 15 sacks cement,
mud to 35', rock bridge with
10 sacks cement.

MISSION
MAY 2 1958
WICHITA, KANSAS
5/21/58

Name of Plugging Contractor Southwest Casing Pulling Company, Inc.
Address P. O. Box 364, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Raymond L. Bacon (employee of ~~owner~~ of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God

(Signature) By: Raymond L. Bacon IMPERIAL OIL OF KANSAS, INC. V-P
780 Fourth National Bldg., Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 20th day of May, 19 58

My commission expires December 19, 1960
Louetta M. Duncan Notary Public.

PLUGGING
FILE SEC. 31 T 7 R 22W
BOOK PAGE 96 LINE 10

15-065-00569-00-00

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Building
Wichita 2, Kansas

MAY
5/21/58

Jones "C" No. 1
C SW SE Sec. 31-7S-22W
Graham County, Kansas

Total Depth: 3935'

Commenced: 3-31-58 Completed: 4-23-58

Elevation: 2286' RB
Production: D & A

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 215' with 150 sacks cement.

Figures indicate bottom of formations:

Rock "Hard"	25'			
Clay & Sand	190'	Anhydrite	1930'	(/ 356)
Sand & Shale	800'	Heebner	3501'	(-1215)
Shells & Shale	1460'	Toronto	3528'	(-1242)
Dakota Sand	1684'	Lansing	3545'	(-1259)
Shale & Red Bed	1930'	Base Kansas City	3751'	(-1465)
Anhydrite	1964'	Arbuckle	3905'	(-1619)
Shale & Shells	2535'	Total Depth	3935'	(-1649)
Shale	2655'			
Shale & Lime	3448'			
Lime	3935'			
Total Depth	3935'			

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: [Signature]
Vice-President

Subscribed and sworn to before me this 1st day of May, 1958.

My Commission Expires:

December 19, 1960

PLUGGING
 FILE SEC. 31 T. 7 R. 22W
 BOOK PAGE 96 LINE 10

[Signature]
Notary Public