

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 30 TWP. 7S RGE. 22W E/W
Location as in quarters or footage from lines:
1610' FEL 1030' FNL NE/4

Locate Well
correctly on above
Section Platt.

Lease Owner Graham-Michaelis Corp.
 Lease Name WEBB Well No. 1-30
 Office Address 801 Union Center, Wichita, KS 67202
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole
 Date Well Completed August 13, 1981
 Application for plugging filed August 13, 1981
 Plugging commenced August 13, 1981
 Plugging completed August 13, 1981
 Reason for abandonment of well or producing formation No commercial quantity of oil or gas encountered.
 Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazar
 Producing formation _____ Depth to top _____ bottom T.D. 3815'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 1st plug @ 950' with 60 sx.
Set 2nd plug @ 300' with 40 sx.
Set 3rd plug @ 40' with 10 sx.
5 sx. in Rathole, 50-50 posmix, 6% Gel.
Plug was down @ 9:15 p.m., 8/13/81.

RECEIVED
STATE CORPORATION COMMISSION
1981
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Abercrombie Drilling, Inc. 8/20/81


STATE OF Kansas COUNTY OF Sedgwick, ss.
Jack L. Partridge, Vice Pres. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack L. Partridge
801 Union Cntr., Wichita, KS 67202
 (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of August, 19 81

My Commission expires: 7-13-85

Elizabeth G. Terry
 Elizabeth G. Terry Notary Public



15-065-21454-00-00

CONTRACTORS WELL LOG

OPERATOR: Graham-Michaelis Corp.
 CONTRACTOR: Abercrombie Drilling, Inc.
 WELL NAME: WEBB #1-30
 LOCATION: 1610' FEL 1030' FNL NE/4, Sec. 30-7S-22W, Graham County, KS
 SPUD DATE: 7/25/81
 COMPLETION DATE: 8/13/81

0	316	Shale & Sand
316	991	Shale
991	1804	Shale & Sand
1804	1836	Anhydrite
1836	2857	Shale
2857	3243	Shale & Lime
3243	3410	Lime & Shale
3410	3540	Shale & Lime
3540	3660	Lime
3660	3756	Conglomerate & Lime
3756	3815	Conglomerate & Dolomite
	3815	Rotary Total Depth

Spud hole @ 5:15 p.m., 7/25/81. Drilled 316' of a 12 1/4" hole. Ran 7 joints of new 23# casing set @ 314' RTD. Cemented with 230 sx. of common 3% c.c., 2% gel. Cement did circulate. Plug was down @ 10:00 p.m., 7/25/81.

3815' RTD. Set 1st plug @ 950' with 60 sx. Set 2nd plug @ 300' with 40 sx. Set 3rd plug @ 40' Solid Bridge with 10 sx. 5 sx. in Rathole, 50-50 posmix, 6% gel. Plug was down @ 9:15 p.m., 8/13/81.

SAMPLE TOPS:

Anhydrite 1804'
 B/ Anhydrite 1836'

RECEIVED
 STATE CORPORATION COMMISSION

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

CONSERVATION DIVISION
 Wichita, Kansas


8/20/81

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the WEBB #1-30, 1610' FEL 1030' FNL NE/4, Sec. 30-7S-22W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.

BY: Jack L. Partridge
 Jack L. Partridge, Vice Pres.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 18th day of August, 1981.



Elizabeth G. Terry
 Elizabeth G. Terry
 NOTARY PUBLIC

my commission expires 7-13-85