

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

RECEIVED  
DEC 02 2005

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

KCC WICHITA

Lease Operator: Liberty Operations & Completions, Inc.

Address: 308 West Mill Plainville KS 67663

Phone: (785) 434-4686 Operator License #: 8925

Type of Well: OIL Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: Emergency Plugging 11-21-05 (Date)

by: Richard Williams (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (If needed attach another sheet)

Toronto & L.K.C. Depth to Top: 3114 Bottom: 3360 T.D. 3451

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	202	0
				5 1/2	3418	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Attempt wash down, got out of hole @ 1720', Lost 14 Joints 2 7/8" tubing with 4 7/8" bit on bottom, Ran 2 7/8" tubing to top fish 1320' circulate 175 sx 60/40 poz 10% gel. Pulled tubing to 800' and circulate 25 sx to surface, pull tubing and squeeze down 5 1/2" casing 10 sx @ 500#

Name of Plugging Contractor: Allied Cementing Co. License #: N/A

Address: Russell, Kansas

Name of Party Responsible for Plugging Fees: Roger L. Comeau

State of Kansas County, Rooks, ss.

Liberty Operations & Completions, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Roger L. Comeau

(Address) 308 West Mill Plainville, KS 67663

SUBSCRIBED and SWORN TO before me this 30 day of November, 20 05

Sandra Chard My Commission Expires: 9/15/06  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC  
BEM  
1-17-06  
RSDMS  
CP 213  
Intented  
Depths  
Listed  
Dist 4

*B...*