

DISTRICT CONSERVATION AGENT'S REPORT

15-065-00221-00-00

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 138-4

LOCATION SW SW SW

SEC. 6 TWP. 7 RGE. 21

Dry Hole  Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Ridgley

Operator A. E. Keating Address 510 Natl Bk Bldg Tulsa,

Field \_\_\_\_\_ County Graham

Total Depth ~~3755~~ 3810 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 280' circulated with cement - 5 1/2" at 3753 with 75  
sax cement behind. Lane Wells plugs to 3681'- top Perforations  
at 3651'.

Chat to 3640', set 4 sax cement with dump bailer, pulled 1035'  
5 1/2", hole mudded to 280', rock to 270', set 15 sax cement, mud  
to 35', set rock and 10 sax cement to bottom cellar.

Mudding by Sun Cementing Co.

2-1-52

STATE CORPORATION COMMISSION

FEB 1 X 1952

CONSERVATION DIVISION  
KANSAS

Edmond Perry  
District Conservation Agent

Date \_\_\_\_\_

1-27-52

PLUGGING  
FILE SEC 6 T 7 R 21 W  
BOOK PAGE 138 LINE 4