

15-065-20661-00-00

~~KANSAS~~

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 4 1974  
CONSERVATION DIVISION  
Wichita, Kansas

11/4/74

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name T. I. Leben & Associates,  
Complete Address 1555 E. Second St., Wichita, Kansas.  
Lease Name Davis Well No. 1  
Location ~~NW SW SE~~ SW NW SE Sec. 30 Twp. 7 Rge. (E) (W) 22  
County Graham Total Depth 3680'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Murfin Drilling Company,  
Address 617 Union Center, Wichita, Kans. License No.         
Operation Completed: Hour 10:00 AM Day 27 Month 10 Year 1974

The above well was plugged as follows:

262'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 110 Cu. Ft. cement  
thru DP from 975' to 650'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Nichols  
Well Plugging Supervisor

INVOICED

DATE 11/4/74  
INV. NO. 247-W