

State of Kansas



15-065-00872-00-04

ROBERT B. DOCKING  
DALE E. SAFFELS  
JULES V. DOTY  
JAMES O. GREENLEAF  
RAYMOND B. HARVEY  
JACK GLAVES

Governor  
Chairman  
Commissioner  
Commissioner  
Secretary  
Gen. Counsel

## State Corporation Commission

### CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

#### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUN 2 1969

CONSERVATION DIVISION  
Wichita, Kansas

6/2/69

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. D. B. Pulley of Forbes Casing Pulling Co., has this date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Chas. L. Carlock,

Complete Address: 1515 Hillcrest, Newton, Kansas.

Lease Name: Worcester Well No. 1

Location: NE-NE-NE Sec. 33 Twp. 7 Rge. (E)(W) 22

County: Graham Total Depth 3832 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

200'--8 5/8" Surface casing, cement circulated.

3832'--4 1/2" Production casing cemented on bottom with 200 Sx. Well plugged back to 3640'. Top perforations @ 3603'.

Sand well back to 3575' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 130 Sx. cement, staged.

Very truly yours,

*W. L. Nichols*

Conservation Division Agent