



15-065-20368-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1970
CONSERVATION DIVISION
Wichita, Kansas

9/21/70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Leo Swords of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Swords guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center Building, Wichita, Kansas.

Lease Name: Hansen Well No. 1

Location: NE-SE-NW Sec. 32 Twp. 7 Rge. (E)(W) 22

County: Graham Total Depth 3475' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Swords was instructed to plug the well as follows:

261'---8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 750'.

Circulate hole with heavy mud. Pull DP to 975' and displace 100 Sx. cement thru DP. Pull DP to 285' and displace 25 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent