

15-065-20542-00-00

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1972
CONSERVATION DIVISION
Wichita, Kansas
4/26/72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Martin Explorations,

Complete Address: 527 Union Center, Wichita, Kansas.

Lease Name: Jones Well No. 1

Location: SE-SE-SE Sec. 31 Twp. 7 Rge. (E)(W) 22

County: Graham Total Depth 3662' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

238'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 750'.

Circulate hole with heavy mud. Pull DP to 975' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hyls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent