

15-065-20542-00-00

Form CP-3
Rev. 6-4-68

KANSAS

 STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT **RECEIVED**
STATE CORPORATION COMMISSION

APR 26 1972

CONSERVATION DIVISION
Wichita, Kansas

4/26/72

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Martin Explorations,

Complete Address 527 Union Center Building, Wichita, Kansas.

Lease Name Jones Well No. 1

Location SE-SE-SE Sec. 31 Twp. 7 Rge. (E) (W) 22

County Graham Total Depth 3662'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.

Operation Completed: Hour 4:00 PM Day 23 Month 4 Year 1972


The above well was plugged as follows:

238'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 110 Cu. Ft. cement
thru DP from 975' to 650'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: 
Well Plugging Supervisor

DATE 4-27-72

INV. NO. 5640-4