

15-065-20368-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

9/21/70

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 21 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company,  
Complete Address 617 Union Center Building, Wichita, Kansas.  
Lease Name Hansen Well No. 1  
Location NE-SE-NW Sec. 32 Twp. 7 Rge. (E) (W) 22  
County Graham Total Depth 3475'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
Other well as hereafter indicated         
Plugging Contractor Above  
Address        License No.         
Operation Completed: Hour 10:15 AM Day 17 Month 9 Year 1970

The above well was plugged as follows:

261'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 750'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 100 Sx. cement thru  
DP from 975' to 650'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from  
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 9-21-70

INV. NO. 2565-w