

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
211 North Broadway  
Wichita, Kansas

FILE NO. 15065-00173-00-00  
147-40  
LOCATION SE SE SE  
SEC. 32 TWP. 7 RGE. 22

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Morris

Operator Murfin Drg Co & Sitrin Address Murfin Drg Wichita, Kans

Field \_\_\_\_\_ County Graham

Total Depth 5786 Feet.

Plugging Contractor Ace Pipe Pulling

Plugging Contractor's License No. 2

Address \_\_\_\_\_

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 172' circulated with cement - 5 1/2" at 5760' - P. B. 5500', perforated at 5450'.

Filled with sand to 5455', set 4 sax cement with dump bailer, pulled 1700' 5 1/2" - to 1200', circulated hole with 40 sax Gel at 1200', pulled pipe to 800', set plug and pumped 40 sax cement through 5 1/2" at 800' - heavy mud to 55', set cementing plug, rock and 10 sax cement to bottom cellar.

*Edna Lee*

District Conservation Agent

Date 3-24-57

PLUGGING  
FILE SEC 32 T 7 R 22 W  
BOOK PAGE 147 LINE 40

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 30 1957  
3/30/57