

15-065-20215-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

5/9/69
RECEIVED
STATE CORPORATION COMMISSION
MAY 9 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Shields Oil Producers, Incorporated,

Complete Address: Shields Building, Russell, Kansas.

Lease Name Jones Well No. A-1

Location SE-SE-NW Sec. 31 Twp. 7 Rge. (E) (W) 22

County Graham Total Depth 3890'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Shields Drilling Company, Incorporated,

Address: Shields Bldg., Russell, Kansas. License No. _____

Operation Completed: Hour 9:15 AM Day 4 Month 5 Year 1969

The Above well was plugged as follows:

248'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 850'.

Circulated hole with heavy mud. Pulled DP to 1065' and displaced 100 Sx. cement thru
DP from 1065' to 760'. Pulled DP to 275' and displaced 20 Sx. cement thru DP from
275' to 215'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 5/9/69
INV. NO. 9736-W