

KANSAS

*TS*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

APR 3 1967

4/3/67

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Aspen Drilling Company,

Complete Address: Box # 783, Great Bend, Kansas.

Lease Name Sayers Estate Well No. 1

Location SW-SE Sec. 36 Twp. 7 Rge. (E) (W) 22

County Graham Total Depth 3660

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Above

Address:      License No.     

Operation Completed: Hour 3:30PM Day 29 Month 3 Year 1967

The Above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 175 Sx.

Circulated hole with heavy mud, set plug @ 540' and displaced 20 Sx.

cement thru DP. Heavy mud to 210', set plug with 1/4 sack hulls and dis-

placed 20 Sx. cement thru DP. Heavy mud to 40', set plug with 1/2 sack

hulls and 10 Sx. cement to bottom of cellar.

    

    

    

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/3/67

INV. NO. 4993-W

Signed: M. L. Nichols  
Well Plugging Supervisor