

15-065-00872-00-01

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

6/2/69
RECEIVED
STATE CORPORATION COMMISSION
JUN 2 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chas L. Carlock,
Complete Address 1515 Hillcrest, Newton, Kansas.
Lease Name Worcester Well No. 1
Location NE-NE-NE Sec. 33 Twp. 7 Rge. (E) (W) 22
County Graham Total Depth 3832'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Forbes Casing Pulling, Incorporated,
Address Box #221, Great Bend, Kansas. License No. 49
Operation Completed: Hour 11:45 AM Day 30 Month 5 Year 1969

The above well was plugged as follows:

200'---8 5/8" Surface casing, cement circulated.
3832'---4 1/2" Production casing cemented on bottom with 200 Sx. Well plugged back to
3640'. Top of perforations @ 3603'.
Sanded well back to 3575' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing
and squeezed well initially with 5 sacks hulls and 19sacks gel and followed with 100
Sx. cement from 850' to 525' then 8 sacks gel from 525' to 205' and followed with 20
Sx. cement from 205' to 145' then 3 sacks gel from 145' to 30' and finally 10 Sx.
cement from 30' to bottom of cellar. Max pump-in pressure--350#. Final shut-in
pressure--100#. Recovered 2100' 4 1/2" casing. (Mudding & Cementing by Allied Cementing).

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 6/2/69
INV. NO. 9864-4

Signed: N. L. Nichols
Well Plugging Supervisor