

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Carmen Schmitt Inc. Address: PO Box 47, Great Bend, KS 67530 Phone: (620) 793-5100 Operator License #: 6569 Type of Well: oil Docket #: The plugging proposal was approved on: December 2005 by: Herb Deines Is ACO-1 filed? No If not, is well log attached? No Producing Formation(s): Arbuckle Depth to Top: ~3967' Bottom: T.D. 3985'

API Number: 15-195-00876-00-00 Lease Name: Ogallah Unit Well Number: 16-2 Spot Location (QQQQ): - NE - NW - SE 2310 Feet from North / South Section Line 1650 Feet from East / West Section Line Sec. 36 Twp. 12 S. R. 22 East / West County: Trego Date Well Completed: June 1953 Plugging Commenced: 12/13/2005 Plugging Completed: 12/15/2005

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows show casing from 0 to 248' and 0 to 3978'.


Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

MIRU, perf at 950', ran 65 joints of 2 3/8" tubing to 2000'. Mix 145 sacks of 60-40 pozmix, 10% gel, with 4 sacks of hulls. Circulated cement. Laid tubing out. Tied on surface casing, pressured to 500 psi, held. Tied on production casing, mixed 35 sacks cement and 1 sack hulls, pressured to 800 psi and shut in. Roger Moses of KCC on hand.

RECEIVED DEC 23 2005 KCC WICHITA

Name of Plugging Contractor: DS&W Well Service License #: 6901 Address: PO Box 231, Claflin, KS 67525 Name of Party Responsible for Plugging Fees: Carmen Schmitt Inc. State of Kansas County, Barton, ss. Jacob L. Porter

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Jacob L Porter (Address) PO Box 47, Great Bend, KS 67530

SUBSCRIBED and SWORN TO before me this 22nd day of December, 20 05. Elaine Schreck Notary Public My Commission Expires: 12-13-07

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Handwritten signature/initials.

ALLIED CEMENTING CO., INC. 23581

Federal Tax I.D.# ~~92-0700000~~

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>12-15-05</u>	SEC. <u>36</u>	TWP. <u>12</u>	RANGE <u>22</u>	CALLED OUT	ON LOCATION <u>8:30am</u>	JOB START <u>9:00am</u>	JOB FINISH <u>11:45</u>
LEASE <u>Ogallah Unit</u>	WELL # <u>16-2</u>	LOCATION <u>T-70 1 Ogallah</u>	<u>15 2 1/2 E</u>		COUNTY <u>Trego</u>	STATE <u>K</u>	
OLD OR NEW (Circle one)		<u>1.5 Winko</u>					

CONTRACTOR D.S. & W
 TYPE OF JOB Old Hole Plug
 HOLE SIZE _____ T.D. _____
 CASING SIZE 5 1/2" DEPTH _____
 TUBING SIZE 2 3/8" DEPTH 2000
 DRILL PIPE _____ DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX 800psi MINIMUM _____
 MEAS. LINE _____ SHOE JOINT _____
 CEMENT LEFT IN CSG. _____
 PERFS. _____
 DISPLACEMENT _____

OWNER _____
 CEMENT Used 180 sks 1.5 Hulls
 AMOUNT ORDERED 375 sks 60/40 10% brk
800# Hulls
500#

COMMON	<u>108</u>	@	<u>870</u>	<u>93960</u>
POZMIX	<u>72</u>	@	<u>470</u>	<u>33840</u>
GEL	<u>12</u>	@	<u>1400</u>	<u>16800</u>
CHLORIDE		@		
ASC		@		
<u>Hulls</u>	<u>5</u>	@	<u>2100</u>	<u>10500</u>
		@		
		@		
		@		
		@		
		@		
		@		
		@		
		@		
		@		
		@		
		@		
HANDLING	<u>410</u>	@	<u>160</u>	<u>65600</u>
MILEAGE	<u>64/sk/mile</u>			<u>135300</u>
				TOTAL <u>356000</u>

RECEIVED

DEC 23 2005

KCC WICHITA

EQUIPMENT

PUMP TRUCK CEMENTER Steve
 # 409 HELPER Craig
 BULK TRUCK
 # 396 DRIVER Jody
 BULK TRUCK
 # _____ DRIVER _____

REMARKS:

Mix 145 sks 1 4 Hulls down tubing & circ.
Cement out 5 1/2"
Tie on to 5 1/2" & Mix 35 sks 1 Hull
Shut in @ 800psi Could not pump into
8 1/2"

Thank You

CHARGE TO: Carmen Schmitt
 STREET _____
 CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB				
PUMP TRUCK CHARGE				<u>60000</u>
EXTRA FOOTAGE		@		
MILEAGE	<u>55</u>	@	<u>500</u>	<u>27500</u>
MANIFOLD		@		
		@		
		@		
				TOTAL <u>87500</u>

PLUG & FLOAT EQUIPMENT

		@		
		@		
		@		
		@		
		@		
				TOTAL _____

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Kurt Chaw

PRINTED NAME